



	SCHEDULE OF DRAWINGS	
SHEET #	TITLE	REV
EW000	COVER SHEET & LOCATION DIAGRAM	А
EW001	GENERAL NOTES	А
EW100	EXISTING SITE PLAN - STAGE 4	А
EW200	SCHEME PLAN - ENTIRE SITE	А
EW201	SCHEME PLAN - STAGE 3	А
EW300	EROSION SEDIMENT CONTROL PLAN	А
EW301	EROSION SEDIMENT CONTROL PLAN - SAND BORROW PIT AREA	А
EW310	EROSION SEDIMENT CONTROL TYPICAL DETAILS - SHEET 1	А
EW311	EROSION SEDIMENT CONTROL TYPICAL DETAILS - SHEET 2	А
EW312	EROSION SEDIMENT CONTROL TYPICAL DETAILS - SHEET 3	А
EW313	EROSION SEDIMENT CONTROL TYPICAL DETAILS - SHEET 4	А
EW400	FINISHED LEVELS PLAN	А
EW410	PEAT STRIP PLAN	А
EW411	PEAT STRIP PLAN - SAND BORROW PIT AREA	А
EW420	SAND BULK EARTHWORKS PLAN	А
EW421	SAND BULK EARTHWORKS PLAN - SAND BORROW PIT AREA	А

PROPOSED DETAIL DESIGN EARTHWORKS PLANS



IMPORTANT NOTE: PRODUCER STATEMENTS

PS4 WILL NOT BE ISSUED AT COMPLETION OF WORKS UNLESS ALL REQUIRED TESTS AND INSPECTIONS HAVE BEEN NOTIFIED TO COOK COSTELLO AND COMPLETED DURING CONSTRUCTION

Cook | costello

FOR WFH PROPERTIES LTD, THE LANDING, STAGES 4 & 5, **ONE TREE POINT**

WDC REF: SD1800110

JOB NO:14333-004 DATE: 01 AUGUST 2019

GENERAL

G1: THIS SET OF DRAWINGS IS TO BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATION AND ALL OTHER CONTRACT DRAWINGS.

G2: THE DRAWINGS ARE A DIAGRAMMATIC REPRESENTATION OF THE WORK TO BE CARRIED OUT ONLY AND DIMENSIONS SHALL NOT BE OBTAINED BY SCALING.

G3: ALL DISCREPANCIES SHALL BE REFERRED TO THE ENGINEER FOR DECISIONS BEFORE PROCEEDING WITH THE WORK.

G4: THE CONTRACTOR IS TO CONFIRM THE LOCATION AND LEVEL OF ALL UNDERGROUND SERVICES PRIOR TO UNDERTAKING ANY EARTHWORKS OR FOUNDATION CONSTRUCTION.

G5: ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE CURRENT CODES OF PRACTICE EXCEPT WHERE VARIED BY THE PROJECT SPECIFICATION AND/OR DRAWINGS:

- NZS 3101:2017 CONCRETE STRUCTURES STANDARD
- NZS 3109 CONCRETE CONSTRUCTION
- NZS 3121 WATER AND AGGREGATE FOR CONCRETE
- AS/NZS 4671 STEEL REINFORCING MATERIALS

G6: GENERAL ABBREVIATIONS

- NTS NOT TO SCALE
- **UNO UNLESS NOTED OTHERWISE**
- FFL FINISHED FLOOR LEVEL
- EGL EXISTING GROUND LEVEL
- FGL FINISHED GROUND LEVEL

G7: WHERE PROPRIETARY PRODUCTS ARE SPECIFIED IN THE DOCUMENTS THE CONTRACTOR MAY SUBMIT AN ALTERNATIVE PRODUCT FOR APPROVAL AND SUBJECT TO WDC APPROVAL.

G8: ALL WORKS ARE TO COMPLY WITH THE HEALTH & SAFETY AT WORK ACT 2015.

G9: ALL WORKS TO COMPLY WITH THE WHANGAREI DISTRICT COUNCIL (WDC) ENGINEERING STANDARDS 2010, THE WDC QUALITY ASSURANCE / QUALITY CONTROL MANUAL VESTED ASSETS. THE WDC ENGINEERING PLAN APPROVAL LETTER. AND NZS4404:2010.

G10: WDC STANDARD DETAILS HAVE NOT BEEN INDEPENDENTLY VERIFIED BY COOK COSTELLO. WE HAVE ACCEPTED THAT THEY WILL PERFORM FOR THE REQUIRED LIFE EXPECTANCY AS STATED IN THE WDC EES 2010. WE ACCEPT NO LIABILITY IF THE STANDARD DETAILS DO NOT ACHIEVE THIS DESIGN LIFE.

G11: WDC INSPECTIONS REQUIRED IN ACCORDANCE WITH EES, ONLY WDC APPROVED CONTRACTORS TO WORK ON WDC RETICULATION (OR THAT TO VEST), REINSTATEMENT, WRITTEN APPROVAL PRIOR TO UNDERTAKING WORKS WITHIN PRIVATE PROPERTY, WORKS ARE TO COMPLY WITH EES, CONTRACTOR IS RESPONSIBLE FOR LOCATING SERVICES PRIOR TO EXCAVATION, AS-BUILT REQUIREMENTS ETC. WDC TO PROVIDE WRITTEN CERTIFICATION WHERE THEY UNDERTAKE TESTING AND INSPECTION.

G12: THE CONTRACTOR MUST REINSTATE AND/OR REPAIR DAMAGE TO THE KERB & CHANNELING AND FOOTPATH ALONG THE PROPERTY ROADSIDE FRONTAGE. REFER EES 2010 (CLAUSE 1.10.9).

G13: SITE SURVEY, EXISTING SEWER, STORMWATER, AND POTABLE WATER, BASED ON DIGITAL AS-BUILT DATA RECEIVED. COORDINATES ARE IN TERMS OF NZGD 2000 MT EDEN CIRCUIT 2000. VERTICAL DATUM IN TERMS OF ONE TREE POINT 1964. ALL LEVELS AND CONNECTION POINTS TO BE CHECKED AND CONFIRMED ON SITE PRIOR TO CONSTRUCTION.

G14: EROSION CONTROL - ALL SILT CONTROL MEASURES SHALL BE PLACED PRIOR TO COMMENCEMENT OF EARTHWORKS. SUCH MEASURES SHALL BE SUBJECT TO FURTHER ADDITIONS AND ALTERATIONS. WHERE CONSIDERED NECESSARY, AS DIRECTED BY THE PROJECT MANAGER OR COUNCIL, DURING THE PROGRESSION OF WORKS, IT IS ADVISED TO CONTACT NRC PRIOR TO COMMENCEMENT OF EARTHWORKS, AFTER INSTALLATION OF EROSION AND SEDIMENT CONTROL DEVICES TO ENSURE THEY HAVE BEEN INSTALLED TO THE SATISFACTION OF NRC

			F	PROJECT DETAILS	TITLE
	C			WFH PROPERTIES LIMITED	STAGE 4 & 5 DETAIL DESIGN
(C) cook costello	в			THE LANDING	COVER SHEET
			01-08-19	ONE TREE POINT	CONSTRUCTION NOTES
WWW.COCO.CO.NZ	A	1ST ISSUE	KH GM	RUAKAKA	
whangarel Auckland weilington Christchurch	REV.	REVISION DETAILS	DRAWN APP.		

EARTHWORKS

E1: ALL PROJECT PAVEMENT SIZES AND DETAILS INDICATED IN THIS DRAWING SET ARE BASED ON A CBR OF 6%.

E2: ALL SITE EARTHWORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF NZS4431. SOIL BEARING CAPACITY IS TO BE VERIFIED UPON COMPLETION OF SITE EARTHWORKS AND DURING FOUNDATION EXCAVATION TO ENSURE ACTUAL SITE CONDITIONS ARE COMPATIBLE WITH THE INFERRED GEOTECHNICAL MODEL. OVER EXCAVATION AND BACKFILLING WITH ENGINEERED FILL OR SITE CONCRETE MAY BE NECESSARY WHERE SOFT SOIL / FILL IS ENCOUNTERED WITH PRIOR VARIATION APPROVAL

E3: COMPACTION IN BASE OF PIPE TRENCHES TO ACHIEVE CLEGG 10.

E4: NES VALIDATION TESTING TO BE UNDERTAKEN BY A CONTAMINATED LAND SQEP ON TOPSOIL STOCKPILES PRIOR TO USE OR SPREADING. TESTING SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE GUIDELINES SET OUT WITHIN CONTAMINATED LAND MANAGEMENT GUIDELINE NO 5. SITE VALIDATION REPORT IS TO BE COMPLETED PRIOR TO COMPLETION OF WORKS AND SUBMITTED TO COUNCIL.

INSPECTIONS / SITE VISITS REQUIRED

(IF ANY).

11: PRE-CONSTRUCTION SITE MEETING WITH CONTRACTOR, ENGINEER AND WDC PRESENT. NRC TO BE INFORMED OF WORKS ON SITE PRIOR TO COMMENCING WORKS.

12: STRIPPED GROUND INSPECTIONS OF ROADS, ROW'S, CROSSING AND SITE FILL AREAS.

13: CONTROLLED FILL TESTING TO BRING FILL UP TO SUBGRADE LEVELS TO BE CONSTRUCTED IN 200mm MAX LIFTS AND TESTED **EVERY 600mm**

14: FINAL INSPECTION WITH, ENGINEER AND CONTRACTOR TO ENSURE ALL WORKS HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED ENGINEERING PLANS FOR FINAL SIGNOFF

ASBUILT CHECKLIST

AB1: PEAT STRIP SURFACE AND UNDERCUT OF UNSUITABLE MATERIAL

AB2: SUBGRADE BULK EARTHWORKS SAND SURFACE

AB3: PEAT AND TOPSOIL RESPREAD



IMPORTANT NOTE: PRODUCER STATEMENTS

PS4 WILL NOT BE ISSUED AT COMPLETION OF WORKS UNLESS ALL REQUIRED TESTS AND NSPECTIONS HAVE BEEN NOTIFIED TO COOK COSTELLO AND COMPLETED DURING CONSTRUCTION

NOT FOR CONSTRUCTION

DATE CREATED	DRAWN	DESIGNED		APPROVED
01-08-2019	K HANSARD	A PAF	RKER	G McGREGOR
CCL REF NO	SCALE		STATUS	
14333-004	NTS @) A3	FOR	APPROVAL
DWG NUMBER			REVISION	
	EW001			А



NOTES: 1. SEE GENERAL NOTES SHEET EW001. 2. CONTOURS ARE AT 0.2m INTERVALS.

	LEGEND:
	CONTOURS MAJOR
	CONTOURS MINOR
187.5	CONTOUR LABELS
	FENCES
ula ala ala ala	TOP OF BANK
	BOTTOM OF BANK
	DRAIN
	WATER EDGE
	PARCEL BOUNDARY
	ABBUTALL BOUNDARY
	EDGE OF SEAL
	EDGE OF METAL
	KERB
	EDGE OF FOOTPATH
EX-SW ——	EXISTING STORM WATER
— EX-SS —	EXISTING SEWER
W	EXISTING WATER
	EXISTING POWER
C	EXISTING CHORUS
\odot	EX STORMWATER MANHOLE
\bigcirc	EX SEWER MANHOLE
	LIGHT POLE
P	POWER POLES
OEP	POWER PILLAR
\bigcirc	TELECOM DOME
Отр	TELEPHONE POLE
S	SIGN POST
	CESSPIT / SUMP
W	WATER METER
H	FIRE HYDRANT
\heartsuit	VALVE
$\left \right>\right $	GATE

NOT FOR CONSTRUCTION

EW100				А
DWG NUMBER		REVISION		
14333-004	1:2000 @ A3		FOR APPROVAL	
L REF NO	SCALE		STATUS	
01-08-2019	BG AI		P	GM
TE CREATED	DRAWN DESIGNED			APPROVED
	TE CREATED	TE CREATED DRAWN	TE CREATED DRAWN DESIGNED	TE CREATED DRAWN DESIGNED





| 40



NOTES:

SEE CONSTRUCTION NOTES SHEET EW001. 1. 2.

- CONTOURS ARE AT 0.2m INTERVALS.
- ALL 1 IN 1 BATTERS TO HAVE A TEMPORARY 3. SAFETY FENCE ERECTED AT TOP OF BATTER OR OTHER APPROVED SAFETY MANAGEMENT PLAN

	<u>KEY:</u>
	POND
	DIRTY WATER DIVERSION
	STORMWATER CATCHMENT AREA
	EARTH BUND WITH DECANT
	STABILISED CONSTRUCTION ENTRANCE
	STORMWATER FLOW
	STAGE BOUNDARY
	GEOTECH PROTECTED OVERFLOW
SW	PROPOSED STORMWATER
Ø	PROPOSED MANHOLE
EX-SW ———	EXISTING STORMWATER
	EARTHBUND

SEDIMENT POND CALCULATIONS: VOLUME REQURED = 200m³/HA

CATCHMENT AREA 1 CONRTIBUTING CATCHMENT AREA = 5.0HA POND VOLUME REQUIRED = 1000m³

CATCHMENT AREA 2 CONRTIBUTING CATCHMENT AREA = 5.4HA POND VOLUME REQUIRED = 1080m³



- RL 7.0m

SECTION A-A

HORIZONTAL SCALE 1:1000, VERTICAL SCALE 1:200

NOT FOR CONSTRUCTION

DATE CREATED	DRAWN	DESIGNED		APPROVED
01/08/2019	BG	G	М	GM
CCL REF NO	SCALE		STATUS	
14333-004	1:2000 @ A3		FOR APPROVAL	
DWG NUMBER			REVISION	
	EW300			А



NOTES:

3.

SEE CONSTRUCTION NOTES SHEET EW001. 1.

- CONTOURS ARE AT 0.2m INTERVALS.
- 2. ALL 1 IN 1 BATTERS TO HAVE A TEMPORARY SAFETY FENCE ERECTED AT TOP OF BATTER OR OTHER APPROVED SAFETY MANAGEMENT PLAN.

<u>KEY:</u>

POND)

- DIRTY WATER DIVERSION
 - EARTH BUND WITH DECANT
 - STORMWATER FLOW
 - EXTENT OF EARTHWORKS
 - GEOTECH PROTECTED OVERFLOW
 - EARTHBUND
 - STAGE BOUNDARY

SEDIMENT POND CALCULATIONS: VOLUME REQURED = 200m³/HA

<u>CATCHMENT AREA</u> : CONRTIBUTING CATCHMENT AREA = 4.0HA POND VOLUME REQUIRED = 800m³

NOT FOR CONSTRUCTION

DATE CREATED	DRAWN	DESIGNED		APPROVED
01/08/2019	BG	GM		GM
CCL REF NO	SCALE		STATUS	
14333-004	1:1250 @ A3		FOR APPROVAL	
DWG NUMBER			REVISION	
	EW301			А



SILT FENCE DESIGN CRITERIA:

SS %	SLOPE LENGTH (m) (MAX)	SPACING OF RETURNS (m)
	N/A	UNLIMITED
	40	60
	30	50
	20	40
	15	30
	6	20

>440N (ASTM D4632) 0.140 pa (MINIMUM) 0.1-0.5mm (ASTM D4751)

> NOL WORKS UNLESS ALL REQUIRED TESTS AND COSTELLO AND COMPLETED DURING CONSI IMPORTANT NOTE: PRODUCER STATEMENTS SUED AT COMPLETION OF BEEN NOTIFIED TO COOK BE ISS HAVE I WILL NOT PS4 INSF

800mm MINIMUM HEIGHT 2ND LAYER GEOTEXTILE

400mm MINIMUM HEIGHT **1ST LAYER GEOTEXTILE** 1000mm MINIMUM POST DEPTH

SUPER SILT FENCE DESIGN CRITERIA:

SS %	SLOPE LENGTH (m) (MAX)	SPACING OF RETURNS (m)
	UNLIMITED	60
	60	50
	30	40
	30	30
	15	20

NOT FOR CONSTRUCTION

	DATE CREATED	DRAWN	DESIGNED		APPROVED
AILS	01-08-2019	K HANSARD	A	Р	GM
	CCL REF NO	SCALE		STATUS	
	14333-004	NTS @) A3	FOR	APPROVAL
	DWG NUMBER			REVISION	
		EW310			А

STABILISED CONSTRUCTION ENTRANCE SPECIFICATIONS:

APPLICATION

USE A STABILISED CONSTRUCTION ENTRANCE AT ALL POINTS OF CONSTRUCTION SITE INGRESS AND EGRESS WITH A CONSTRUCTION PLAN LIMITING TRAFFIC TO THESE ENTRANCES ONLY. THEY ARE PARTICULARLY USEFUL ON SMALL CONSTRUCTION SITES BUT CAN BE UTILISED FOR ALL PROJECTS.

DESIGN:

- CLEAR THE ENTRANCE AND EXIT AREA OF ALL VEGETATION, ROOTS AND OTHER UNSUITABLE MATERIAL AND PROPERLY GRADE IT.
- 1. LAY WOVEN GEOTEXTILE; PIN DOWN EDGES AND OVERLAP JOINTS.
- 2. PROVIDE DRAINAGE TO CARRY RUNOFF FROM THE STABILISED CONSTRUCTION ENTRANCE TO A SEDIMENT CONTROL MEASURE.
- 3. PLACE AGGREGATE TO THE SPECIFICATIONS BELOW AND SMOOTH IT.
- 4. STABILISED CONSTRUCTION ENTRANCE AGGREGATE SPECIFICATIONS:

AGGREGATE SIZE	5-150mm WASHED AGGREGATE
THICKNESS	150mm MINIMUM OR 1.5 X AGGREGATE SIZE
LENGTH	10m MINIMUM LENGTH RECOMMENDED
WIDTH	4m MINIMUM

MAINTENANCE

- 1. MAINTAIN THE STABILISED CONSTRUCTION ENTRANCE IN A CONDITION TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. AFTER EACH RAINFALL INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT FROM THE STABILISED CONSTRUCTION ENTRANCE AND CLEAN OUT AS NECESSARY.
- 2. WHEN WHEEL WASHING IS ALSO REQUIRED, ENSURE THIS IS DONE ON AN AREA STABILISED WITH AGGREGATE WHICH DRAINS TO AN APPROVED SEDIMENT RETENTION FACILITY.



PROJECT DETAILS TLE С WFH PROPERTIES LIMITED STAGE 4 & 5 DETAIL DESIGN cook | costello THE LANDING EROSION SEDIMENT CONTROL DETAIL в ONE TREE POINT SHEET 2 01/08/2019 **1ST ISSUE** A www.coco.co.nz BG GM RUAKAKA Whangarei | Auckland | Wellington | Christchurch REVISION DETAILS DRAWN APP. REV.

	01/08/2019	BG	G	М	GM
JI S	CCL REF NO	SCALE		STATUS	
	14333-004	NTS @) A3	FOR	APPROVAL
	DWG NUMBER			REVISION	
		EW311			А
DO NOT REPRODUCE WITH					TTEN AUTHORITY

NOT FOR CONSTRUCTION DATE CREATED DRAWN DESIGNED APPROVED

PS4 WILL NOT BE ISSUED AT COMPLETION OF WORKS UNLESS ALL REQUIRED TESTS AND INSPECTIONS HAVE BEEN NOTIFIED TO COOK COSTELLO AND COMPLETED DURING CONSTRUCTION

IMPORTANT NOTE: PRODUCER STATEMENTS

G. M. MCGREGOR WDC IQP#002



		R DECANT OP 1/3 OF LIVE ST	ERATES	OVER DNLY		
		LE DECANT OI 2/3 OF LIVE ST	PERATES ORAGE (S OVER DNLY		
/		ER DECANT OF DEPTH OF LIV D 1500mm	PERATES E STORA	OVER AGE		
	↓ ↓ 500mm → WARATAH → REFER DE	DEAD STORA STAKES REQU CANT DETAIL	AGE JIRED FC)r all i	DETAILS	
)WARAT NYLON LEVEL (AHS AND CORD TO OF DECA	9 STROP D CONT NT	NG ROL	
I NTION I	POND					
NUMBER OF DECANTS FOR EACH POND SHALL BE AS FOLLOWS: I) UP TO 1.5HA CATCHMENT - 1 DECANT II) 1.5-3.0HA CATCHMENT - 2 DECANTS III) 3 TO 5 HA CATCHMENT - 3 DECANTS						
GM2						
G. M. MCGREGOR WDC IQP#002						
	DATE CREATED 01/08/2019	DRAWN BG		м	APPROVED GM	
AILS	CCL REF NO 14333-004	SCALE NTS	@ A3	STATUS	APPROVAL	
	DWG NUMBER	EW312		REVISION	A	
		DO NOT REPRO	DUCE WITH	IOUT WRI	I I EN AUTHORITY	









CUT / FILL DEPTHS Lower_value Upper_value Colour-300to-8mImage: Colour-300to-8mImage: Colour-8to-7mImage: Colour-7to-6mImage: Colour-6to-5mImage: Colour-5to-4mImage: Colour-4to-3mImage: Colour					
-300 to -8 m -8 to -7 m -7 to -6 m -6 to -5 m -5 to -4 m	CUT / F Lower_	ILL DE	PTHS Upper	value	Colour
-8 to -7 m -7 to -6 m -6 to -5 m -5 to -4 m	-300	to	-8	m	
-7 to -6 m -6 to -5 m -5 to -4 m -4 to -3 m	-8	to	-7	m	
-6 to -5 m -5 to -4 m -4 to -3 m	-7	to	-6	m	
-5 to -4 m	-6	to	-5	m	
-4 to -3 m	-5	to	-4	m	
	-4	to	-3	m	
-3 to -2 m	-3	to	-2	m	
-2 to -1 m	-2	to	-1	m	
-1 to5 m	-1	to	5	m	
5 to25 m	5	to	25	m	
25 to 0 m	25	to	0	m	
0 to .25 m	0	to	.25	m	
.25 to .5 m	.25	to	.5	m	
.5 to 1 m	.5	to	1	m	
1 to 2 m	1	to	2	m	
2 to 3 m	2	to	3	m	
3 to 4 m	3	to	4	m	
4 to 5 m	4	to	5	m	
5 to 6 m	5	to	6	m	
6 to 7 m	6	to	7	m	
7 to 8 m	7	to	8	m	
8 to 300 m	8	to	300	m	

PT LOT 7 DP 23910

QUANTITIES:

TOPSOIL STRIP AREA = 100,370m² TOTAL TOPSOIL STRIP 180mm THICK = 18,067m³ TOTAL PEAT STRIP = 62,970m³

VOLUMES BASED ON COMPARISON BETWEEN EXISTING TOPO DATA AND ASSUMED TOP OF SAND LAYER.

NOTES

- QUANTITIES BASED ON INFORMATION RECEIVED 1. FROM WOODS CONSULTANTS. THE TOP OF SAND SURFACE HAS BEEN INFERRED BASED ON GEOTECHNICAL TESTING AND WILL NEED TO BE CONFIRMED ON SITE DURING EXCAVATION.
- VOLUME ABOVE IS BASED ON SOLID MEASURE. IT 2. IS RECOMMENDED THAT FURTHER ADJUSTMENTS BE MADE TO THE VOLUMES MENTIONED ABOVE TO ALLOW FOR ITEMS SUCH AS BULKING FACTORS AND PAVEMENT BOXING.
- 3. ALL 1 IN 1 BATTERS TO HAVE A TEMPORARY SAFETY FENCE ERECTED AT TOP OF BATTER OR OTHER APPROVED SAFETY MANAGEMENT PLAN

NOT FOR CONSTRUCTION

DATE CREATED	DRAWN	DESIGNED		APPROVED
01-08-2019	K HANSARD	K HANSARD 🛛 A PAF		G McGREGOR
CCL REF NO	SCALE		STATUS	
14333-004	1:2000 @ A3		FOR APPROVAL	
DWG NUMBER			REVISION	
	EW410			А



NOTES: 1. SEE CONSTRUCTION NOTES EW001 2. CONTOURS ARE AT 0.2m INTERVALS.

CUT / FILL DEPTHS Lower_value Upper_value Colour					
-300	to	-8	m		
-8	to	-7	m		
-7	to	-6	m		
-6	to	-5	m		
-5	to	-4	m		
-4	to	-3	m		
-3	to	-2	m		
-2	to	-1	m		
-1	to	5	m		
5	to	25	m		
25	to	0	m		
0	to	.25	m		
.25	to	.5	m		
.5	to	1	m		
1	to	2	m		
2	to	3	m		
3	to	4	m		
4	to	5	m		
5	to	6	m		
6	to	7	m		
7	to	8	m		
8	to	300	m		

SAND BULK EARTHWORKS QUANTITIES: TOTAL EARTHWORKS AREA = 107,170m² TOTAL SAND CUT TO FILL = 26,450m³ TOTAL SAND REQUIRED FROM SAND MINE AREA = 26,000m³

SAND CUT: 26,450m3 SAND FILL: 52,450m³

VOLUMES BASED ON COMPARISON BETWEEN ASSUMED TOP OF SAND TO DESIGN SUBGRADE.

TOPSOIL = 200mm RESPREAD ALLOWED FOR. PAVEMENT = PAVEMENT ALLOWED FOR.

NOT FOR CONSTRUCTION

	DATE CREATED 01-08-2019	DRAWN K HANSARD	DESIGNED	RKER	APPROVED G McGREGOR
1	CCL REF NO 14333-004	SCALE 1:2000 (@ A3	status FOR	APPROVAL
	DWG NUMBER	FW/420		REVISION	А
		200420			~

NOTES: SEE CONSTRUCTION NOTES EW001 CONTOURS ARE AT 0.2m INTERVALS. 2.

CUT / FILL DEPTHS Lower_value Upper_value Colour						
-300	to	-8	m			
-8	to	-7	m			
-7	to	-6	m			
-6	to	-5	m			
-5	to	-4	m			
-4	to	-3	m			
-3	to	-2	m			
-2	to	-1	m			
-1	to	5	m			
5	to	25	m			
25	to	0	m			
0	to	.25	m			
.25	to	.5	m			
.5	to	1	m			
1	to	2	m			
2	to	3	m			
3	to	4	m			
4	to	5	m			
5	to	6	m			
6	to	7	m			
7	to	8	m			
8	to	300	m			

SAND BULK EARTHWORKS QUANTITIES: TOTAL EARTHWORKS AREA = 25,200m² TOTAL SAND CUT = 27,680m³

VOLUMES BASED ASSUMED TOP OF SAND TO ASSUMED FUTURE DESIGN

57

260

5

27

27

NOT FOR CONSTRUCTION

	DATE CREATED 01-08-2019	DRAWN K HANSARD	DESIGNED	RKER	APPROVED G McGREGOR
1	CCL REF NO 14333-004	SCALE 1:2000	@ A3	STATUS FOR	APPROVAL
	DWG NUMBER	EW421		REVISION	A